

## **Project:**

Custom ice rink refrigeration package

**Client:** Hector Arena

**Year**: 2022

Solution: Custom ice rink refrigeration package as part of a hockey arena's R22 phaseout



- One skid-mounted 80TR indoor air-cooled ice rink
- Opteon XP10 (R513a) refrigerant
- Two compact screw compressors
- One remote air-cooled condenser
- One dual circuit shell & tube evaporator
- Two centrifugal brine pumps
- Factory testing
- Freight to site



## **Highlights:**



**Custom Engineered** 



Air cooled



Commissioning



**Factory Tested** 



Start-up

Custom ice rink refrigeration package as part of a hockey arena's R22 phaseout. Scope of supply included one skid-mounted 80TR indoor air-cooled ice rink chilled charged with Opteon XP10 (R513a) refrigerant, two compact screw compressors, one remote air-cooled condenser, one dual circuit shell & tube evaporator, two centrifugal brine pumps, factory testing, freight to site, startup and commissioning.

> Call or visit: 1 416-755-2221 www.berg-group.com/rinks